

CEMENT STABILIZED BACKFILL DETAIL




TABLE I: TRENCH BENCH

TRENCH WIDTH	Ⓐ (FEET)*
≤ 3'	1
>3' - ≤6'	2
>6' - ≤9'	3
>9'	W/3**

NOTES:

1. All UTILITIES WITHIN 2 FEET OF THE EDGE OF A PAVED SHOULDER, OR 4 FEET IF NO PAVED SHOULDER EXISTS, OR WHERE EXISTING SURFACE GRADE EXCEEDS 5% SHALL BE REQUIRED TO BE CAPPED WITH CEMENT STABILIZED BASE OR APPROVED EQUIVALENT.

2. THE LIMITS CEMENT STABILIZED BACKFILL WILL BE DETERMINED AT THE TIME A PERMIT IS REVIEWED.

3. A 6" THICKNESS OF CEMENT STABILIZED BASE, BENCHED AS NOTED IN TABLE I ON EACH SIDE OF THE TRENCH WILL BE USED FOR THE FINAL LIFT OF THE TRENCH REPAIR.